

MODULAR HOME, SIP FOUNDATION PROJECTS NORBURN, MO



SIP FOUNDATION FLOOR



SIP INSTALLATION

DESIGN, ENGINEERING, PRODUCT PARTNER
& CONSTRUCTION ASSISTANCE

M.R. & HAMILTON
NORBURN, MO

1,428 SQ.FT. MODULAR HOME, ENERGY EFFICIENT SIP FOUNDATION

FOUNDATION FLOOR: 4 ½" SIP FLOOR R-22 SET ON SLEEPER ON GRAVEL
BED WITH BUILT IN DRAINAGE SYSTEM.

FOUNDATION WALLS: 8 ½" SIP TREATED BOTH SIDES WITH STRUCTURAL
PLYWOOD R-34, BUILT IN STRUCTURAL POINT LOADS AND ALL REQUIRED
WINDOW OPENINGS FOR EGRESS.

SYSTEM WAS INSTALLED BY OWNER W/ON SITE ASSISTANCE FROM EC&D

